

8-17-88

1 030971

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,840-0000

SE SW NW, SEC. 4, T 26 S, R 16 WEX
2999 feet from S section line
4125 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3521

Lease Name Welsch Well # 1

Operator: Ranger Petroleum Corporation
Name & Address: Box 1036
Wichita, KS 67201

County Edwards 147.52

Well Total Depth 4539 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 17 Month: 8 Year: 19 88

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4530' PBTD 4530' Perfs at 4456-59'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

8-23-88

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 17 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 50 psi.

Remarks: Used 50/50 Pozmix 4% gel by B.J. Titan. Recovered 3050' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 8-24-88

WSV. NO. 21907 8-17