

7-28

1 051089

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,845-0000

NW NW NW, SEC. 4, T 26 S, R 16 W/R

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Cudney "A" Well # 6-4

Operator: Sterling Drilling Company

County Edwards 147.39

Name & Address Box 129

Well Total Depth 4535 feet

Sterling, KS 67579

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 28 Month: 7 Year: 19 88

Plugging proposal received from Ronnie Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4531' Perfs at 4428-32'

1st plug sand back to 4470' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1988
9-26-88

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging operations attended by Agent?: All Part None

Operations Completed Hour: 10:05 a.m. Day: 28 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4470' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 0 psi and shut in on vacuum. 9/22/88-cement top 25'GL.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-4-88

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 22457