

1040967

5-5

API NUMBER 15-047-20,865-000

KANSAS CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
430 S. Market, Room 2078  
Wichita, KS 67202

Irreg. sec. SEC. 4, T 26, S, R 16 W/E

330' FNL Lot 4 feet from S section line

330' FEL Lot 4 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cudney A Well # 7

Operator: F.G. Holl Company L.L.C.

County Edwards 149.18

Name: F.G. Holl Company L.L.C.

Address P.O. Box 780167

Well Total Depth 4590 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 449

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 5 Month: 5 Year: 19 95

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

work: 4 1/2" at 4562' w/225 sx cement, PBSD 4403'; Perfs at 4086-87'

1st plug sand back to 4004' and dump 4 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:15 p.m. Day: 5 Month: 5 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4004' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED KANSAS CORPORATION COMMISSION

Maximum pressure 400 psi and shut in 100 psi.

MAY 08 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2307' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form)

INVOICED

Observe this plugging.

DATE 5-16-95

NO. 42831

Signed [Signature] (TECHNICIAN)