

1030344

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,496-~~0000~~ ^R
SW/4, SEC. 3, T 26 S, R 15 W/EX

660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Grizzell "C" Well # 2

Operator: Cities Service Oil & Gas Corp.
Name & Address 800 Sutton Place Building
209 East William
Wichita, KS 67202

County Pratt 147.88

Well Total Depth 4550 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:00 am Day: 11 Month: December Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" set at 4548' PBD 4512'

1st plug push plug to 3835' and dump 5 sx cement on top

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement

Plugging Proposal Received by *Steve Shumant*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 am Day: 11 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2" set at 4548' PBD 4512'

1st plug pushed plug to 3835' and dumped 5 sx cement on top. 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 150 psi and shut in 0

JAN 02 1985

1-2-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2410' 5 1/2" casing. Used common cement with 2% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-14-85

Signed *Steve Shumant*
(TECHNICIAN)

INV. NO. 6403