

To: 1 120532
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-20 15-151-30167-6001 236
API NUMBER 15- Docket #E-15,235
C NE NE, SEC. 10, T 26 S, R 15 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229
Operator: Phillips Petroleum Company
Name & Address: Rt. 3, Box 20-A
Great Bend, KS 67530

Lease Name Gereke Unit Well # 8W-06 (SW-06 on plugging appl.)
County Pratt 139.88
Well Total Depth 4304 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 12 3/4 feet 495

Abandoned Oil Well _____ Gas Well _____ Input Well X SMD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 20 Month: 2 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4188', PBSD 4140', Perfs at 3986-4008'

1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 75 sx cement, 10 sx gel, 1 sx hulls, release 12 3/4" wiper plug and pump 175 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 20 Month: 2 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3900' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 12 3/4" surface casing with 300 lbs. hulls, 5 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, 100 sx cement, 5 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-200 psi and shut in 50 psi.

4 1/2" packer stuck in 4 1/2" casing at 3953'. Welded plate and 5 1/2" collar on surface casing.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2208' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-27-91
INV. NO. 30931
2-20

FEB 22 1991

CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Durrant (TECHNICIAN)

2-22-91