

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-19012-00-01
Spot: NWSW Sec/Twnshp/Rge: 11-26S-15W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: GEREKE UNIT Well Number: 4W 01
County: PRATT Total Vertical Depth: 4368 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

Production Casing Size: 5.5 feet: 4367 125 SX CMT
Surface Casing Size: 8.625 feet: 310 300 SX CMT

96
#141

Well Type: EOR UIC Docket No: E15235.4 Date/Time to Plug: 09/22/2003 11:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JIM BYERS Company: COMPANY TOOLS Phone: (620) 672-9001

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 100 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/22/2003 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:


PBTD 4329'. PERFS AT 3948-4009'.. SANDED BACK TO 3900' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 8 5/8" WIPER PLUG - 100 SX CMT. MAXIMUM PRESSURE 300#. SHUT IN PRESSURE 100#.

RECEIVED
SEP 26 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1402' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 9-26-03
INV. NO. 2004060546

Form CP 2/3