

1 040439

7-10 80-7925 168P  
API NUMBER 15-NA B842638 15-51-19013-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW NW, SEC. 11, T 26 S, R 15 W  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Gereke Well # 5-1

Operator: Phillips Petroleum Company

County Pratt 144.63

Name & Address Rt. 3, Box 20-A

Well Total Depth 4450 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4:15 p.m. Day: 10 Month: 7 Year: 19 90

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4194' Perfs at 3977-81, 3999-4001, 3984-89, 3998-4004, 4107-14'

1st plug sand back to 3925' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Mike Spain  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:45 p.m. Day: 10 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3925' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 4 1/2" casing. JUL 19 1990

(if additional description is necessary, use BACK of this form)

INVOICED (add) observe this plugging.

DATE: 7-27-90

INV. NO. 28786

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
7-19-90

CONSERVATION DIVISION  
Wichita, Kansas