

1041391

TO: STATE CORPORATION COMMISSION

API NUMBER NA 15-151-30010-00-01
SE NW SEC. 11, T 26 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 3330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GEREKE UNIT WELL # 5-W02

TECHNICIAN'S PLUGGING REPORT 3/15

COUNTY PRATT 136.18

OPERATOR LICENSE # 30481

WELL TOTAL DEPTH 4190 FEET

OPERATOR: APOLLO ENERGIES, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4189' WITH SX
TOC at +3590'

NAME AND 734-B NORTH FOUR WHEEL DR.

TUBING: SIZE 2 7/8" @ 4160' WITH 395 SX
Cemented back to surface

ADDRESS KINGMAN, KS 67068

SURFACE CASING: SIZE 8 5/8" @ 307'

ABANDONED OIL WELL GAS WELL INPUT WELL E-15,235 SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR APOLLO ENERGIES, INC LICENSE NUMBER 30481

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 15 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM JIM BYERS

(COMPANY NAME) APOLLO ENERGIES (PHONE) 316-532-2390

WERE: LKC @ 3998-4111 & LKC "A" ZONE @ 3840-46. 1982 SQUEEZED CASING LEAK IN 4 1/2" CASING WITH 375 SX CEMENT.

PUMPED DOWN 2 7/8" TUBING WITH 50# HULLS AND 100 SX CEMENT. MAXIMUM PRESSURE AT 1000#.

SHUT IN PRESSURE AT 300#. PUMPED DOWN 4 1/2/8 5/8" ANNULUS WITH 5 SX CEMENT. PRESSURE UP TO 1000#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 3:15 PM DAY: 15 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT

PUMPED DOWN 2 7/8" TUBING WITH 50# HULLS AND 100 SX CEMENT. MAXIMUM PRESSURE AT 1000#.

SHUT IN PRESSURE AT 300#. PUMPED DOWN 4 1/2/8 5/8" ANNULUS WITH 5 SX CEMENT. PRESSURE UP TO 1000#.

REMARKS: USED 65/35 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED RECEIVED

I (DID) OBSERVE THIS PLUGGING AT STATE CORPORATION COMMISSION

On April report

DATE 5/15/00 SIGNED Stephen J. Pfeifer MAR 22 2000

(TECHNICIAN) FORM CP-2/3

INV. NO. 61724 CONSERVATION DIVISION
Wichita Kansas