

1 040438

7-13 80-7925
8842638

169
15-151-00516-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 12/3/63
SE SW NW, SEC. 11, T. 26 S, R. 15 W

TECHNICIAN'S PLUGGING REPORT

2970 feet from S section line

4290 feet from E section line

Operator License # 5229

Lease Name Gereke Well # 6-1

Operator: Phillips Petroleum Company

County Pratt 145.28

Name & Address Rt. 3, Box 20-A

Well Total Depth 4470 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 13 Month: 7 Year: 19 90

Plugging proposal received from Ronnie Hoover

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4470' PBD 4384' Perfs at 4109-15, 4000-07, 3993-96, 3983-87'

1st plug sand back to 3930' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

Plugging Proposal Received by Mike Spain
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 13 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3930' and put 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
JUL 19 1990
7-19-90
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix .6% gel by Halliburton. Recovered 2104' of 4 1/2" casing. Kansas
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

DATE: 7-27-90

Signed Stephen J. Defer (TECHNICIAN)

INV. NO. 28787