

To: 1 060997
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Company, Inc.
Name & Address: P.O. Box 2758
Wichita, KS 67201

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Box 963, Pratt, KS 67124

Company to plug at: Hour: 1:30 p.m. Day: 15 Month: 9 Year: 19 87

Plugging proposal received from Gene Brown

(company name) Mull Drilling Company, Inc. (phone) 316-254-7382

were: 5 1/2" at 4090' Perfs at 4031-37'

1st plug pump 25 sx cement with 3 sx hulls at 4037' down 5 1/2",

2nd plug pump 50 sx cement at 1000'-0'.

3rd plug pump 75 sx cement down annulus-8 5/8" X 5 1/2".

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls with 25 sx cement,

2nd plug filled hole to 1000' with water spacer and pumped 50 sx cement filling 5 1/2" to 0',

3rd plug pumped 75 sx cement down annulus.

Pumped through tubing.

Maximum pressure 200 psi and shut in 50 psi - 5 1/2".

Maximum pressure 600 psi and shut in 400 psi.- 8 5/8".

Remarks: Used Econolite by Halliburton. No recovery.

(If additional description is necessary, use BACK of this form.)

I hereby acknowledge and observe this plugging.

DATE 9-23-87

INV. NO. 18178

9-15-87 15-151-00054-0000
API NUMBER 15- Completion date 4/15/58

NE NE SW, SEC. 17, T 26 S, R 15 W/EX
2310 feet from S section line
2970 feet from E section line

Lease Name Doggett Well # 1

County Pratt 152.26

Well Total Depth 4685 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1029

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1987 9-17-87

CONSERVATION DIVISION
Wichita Kansas

Signed Paul A. Luttie (TECHNICIAN)