

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-047-20,592-0000

LEASE NAME Cudney

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER B5-4

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR STERLING DRILLING COMPANY

SEC. 4 TWP. 26 RGE. 16W(E) or (W)

ADDRESS P.O. Box 129
 Sterling, KS 67579

COUNTY Edwards

PHONE# (316) 278-2131 OPERATORS LICENSE NO. 5142

Date Well Completed

Character of Well

Plugging Commenced 9/22/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/2/88

The plugging proposal was approved on 9/30/88 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS 10-7-88 CASING RECORD

Formation	From	To	Size	Put In	Pulled out
			8 5/8	424	none
			4 1/2	4533	2381

Describe in detail the procedure which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged bottom with sand to 4370', dumped 5 sacks cement. Shot @2381,
plugged surface with 400# hulls, 10 gel, 50 sacks cement, 10 gel, 100# hulls,
8 5/8 plug, 120 sacks cement 60/40 pos, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STERLING DRILLING COMPANY

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS67524

SUBSCRIBED AND SWORN TO before me this 5th day of October, 19 88

Jane Hoover
 Notary Public

My Commission Expires: 