

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-047-20,683-000

LEASE NAME Cudney

WELL NUMBER B #6-4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 4 TWP. 26 RGE. 16W (E) or (W)

COUNTY Edwards

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR STERLING DRILLING COMPANY

Box 129

ADDRESS Sterling, KS 67579

PHONE# (316) 278-2131 OPERATORS LICENSE NO. 5143

Character of Well

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED
STATE CORPORATION COMMISSION
10-12-88
OCT 12 1988

Date Well Completed

Plugging Commenced 7/22/88

Plugging Completed 9/22/88

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

CONSERVATION DIVISION
Wichita, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4565'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	457	none
				4 1/2	4563	2364

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged bottom with sand to 4400', ran 4sx. cement, Shot @2630', 2435', 2364'. Pumped 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, released plug, 20sx cement, 60/40 pos 6% gel, hole in surface. Plugged surface, drilled out to 1114', pumped 40sx. 60/40 pos 6% gel, @1114', pulled to 465, pumped 40sx, pulled to 30ft., pumped 10sx. (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: STERLING DRILLING COMPANY

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1988

My Commission Expires



Notary Public