

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-047-20745-0000

LEASE NAME Parker A #2

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE SE NW

SEC. 4 TWP. 26S RGE. 16W (E) or (W)

COUNTY Edwards

Date Well Completed \_\_\_\_\_

Plugging Commenced 7/24/85

Plugging Completed 8/1/85

LEASE OPERATOR Oil Producers Inc. of Kansas.

ADDRESS Box 8647, N. Woodlawn, Wichita, Ks. 67208

PHONE # (316) 682-9527 OPERATORS LICENSE NO. 8061

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4495'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	299'	none
				4 1/2"	4494'	3012'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3390' & 4 sacks cement. Shot pipe at 3823', 3426', & 3012'. Pulled 93 joints of pipe. Plugged well with 300# hulls, 10 gel, 50 cement, 10 gel, 100# hulls, plug, & 150 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 85.

My Commission expires: \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public  
AUG 7 1985  
8-7-85  
Form CP-4  
CONSERVATION DIVISION revised 01-84