

API NUMBER 15-047-20, 836-0000  
 LEASE NAME Cudney A  
 WELL NUMBER 5

TYPE OR PRINT  
 NOTICE: Fill out completely and return  
 to Cons. Div. office within 30 days.

330 Ft. from S/R Line of Section (circle one)  
330 Ft. from E/W Line of Section (circle one)

LEASE OPERATOR FG Holl Co. LLC  
 ADDRESS 6427 E. Kellogg Box 180167  
 CITY, STATE, ZIP Wichita, Ks. 67278-0167  
 PHONE# (316) 684-8481 OPERATORS LICENSE NO. 5056  
 Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

SPOT LOCATION Irregular Section  
 SEC. 4 TWP. 26 S. RGE 16 (E) of (W)  
 COUNTY Edwards  
 Date Well Completed \_\_\_\_\_  
 Date Plugging Commenced \_\_\_\_\_  
 Date Plugging Completed 4-28-95

The plugging proposal was approved on 4-26-95 (date)  
 by Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_  
 Producing Formation(s) \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4550

Show depth and thickness of all water, oil and gas formations.

PBTD: 4505

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
		0	440	8 5/8	440	0
		0	4545	4 1/2	4545	2230 ft.

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

3 hulls - 10 gel - 50 sx. cement - 10 gel - 1 hulls - 8 5/8 plug - 150 sx. cement on top. 60-40 poz. 6% gel.  
Top of cement 136 down - filled to surface with Pedi-mix.  
Well was sanded 50' above top perms + 4 sx. cement on top of sand.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pratt Well Service Inc.

License No. 5893

Address PO Box 847 Pratt, Ks. 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: FG Holl Co. LLC

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Berry (Employee of operator or (operator) of above-described well, being first

duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) PO PWS, Inc.

SUBSCRIBED AND SWORN TO before me this 19th day of May, 1995

Dorothy M. Furgason  
 Notary Public

My Commission Expires: 02/06/97

RECEIVED  
 STATE CORPORATION COMMISSION  
5-26-95  
 MAY 26 1995

