

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-151-21,908-0000

LEASE NAME Reiman

WELL NUMBER 1-2

4950 Ft. from S Section Line

4950 Ft. from E Section Line
 *Irregular Section

SEC. 2 TWP. 26S RGE. 15 (E) or (W)

COUNTY PRATT

Date Well Completed 11-8-88

Plugging Commenced 11-8-88 12:30 A.M.

Plugging Completed 11-8-88 1:30 A.M.

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300, Wichita, Kansas 67202

PHONE#(316) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 7, 1988 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? by operator If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4485'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	State Corporation Commission
surface		0	353	8 5/8"	353'	none

RECEIVED
 STATE CORPORATION COMMISSION
 11-14-88
 NOV 14 1988

Describe in detail the manner in which the well was plugged, indicating where the mud or fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50sx. 60/40 Pozmix, 6% gel at 1010', 50 sx 60/40 Pozmix, 6% Gel. at 390', 10 sx. 60/40 Poz 6% Gel. at 40', 15 sx. in rathole TOTAL 125 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Ks. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson
 Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1988



Bessie M. DeWerff
 Notary Public
 Bessie M. DeWerff

My Commission Expires: 5-20-89

15-151-21908-0000

DRILLERS WELL LOG

DATE COMMENCED: 10-31-88
DATE COMPLETED: 11-08-88

MURFIN DRILLING COMPANY
REIMAN #1-2
4950 FSL 4950 FEL
Sec. 2-26S-15W
Pratt County, Ks.

0 - 200 Sand
200 - 330 Red Bed
330 - 2165 Shale
2165 - 2890 Shale W/Lime
2890 - 3490 Lime & Shale
3490 - 3690 Lime
3690 - 4370 Lime & Shale
4370 - 4485 Lime & Chert

ELEVATION: 2026 GL 2031 KB

FORMATION DATA: Log

Heebner 3697 (-1666)
Toronto 3714 (-1683)
Brown Lime 3844 (-1813)
Lansing 3871 (-1840)
BKC 4198 (-2167)
Kinderhook 4335 (-2304)
Viola 4404 (-2373)

SURFACE CASING:

8 5/8" set at 353' W/195 sx. 60/40
Pozmix, 2% Gel, 3% CC

RECEIVED
STATE CONSERVATION COMMISSION
NOV 14 1988
CONSERVATION DIVISION
Wichita, Kansas


A F F I D A V I T

STATE OF KANSAS) ss
COUNTY OF BARTON)

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 9th day of November 1988.



My Commission expires: 5-20-89

Bessie M. DeWerff
Notary Public: Bessie M. DeWerff