


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-151-30006-0000



Locate well correctly on above Section Plat

Pratt County, Sec. 2 Twp. 26S Rge. 15W (E) (W)
Location as "NE/CNWxSWx" or footage from lines C SE SW
Lease Owner Anadarko Production Company
Lease Name Reiman "B" Well No. 2
Office Address Box 351, Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-14 19 65
Application for plugging filed 4-15 19 65
Application for plugging approved 19
Plugging commenced 4-14 19 65
Plugging completed 4-14 19 65
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4350 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	355'	
				4-1/2	4139'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Circulate hole with mud from 386', spotted 25 sxs. cement @ 236', formed rock bridge from 40' to 30', spotted 10 sxs. cement from 30' to surface.

RECEIVED
STATE CORPORATION COMMISSION

APR 22 1965

4-22-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sargent's Casing Pulling Service
Address Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, SS.
V. K. Downey, Supt. Drilling & Production (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. K. Downey
Box 351, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 65

My commission expires _____ My Commission Expires Sept. 29, 1968

Notary Public.

DRILLER'S LOG

15-151-30006-0000

WELL NAME: Reiman "B" No. 2 ; COMPANY OPERATING: Anadarko Production Company
 ADDRESS of COMPANY: Box 351, Liberal, Kansas
 WELL LOCATION: C 1/4 SE 1/4 SW 1/4,
ft. North of South line,
ft. East of West line; Sec. 2, Twp. 26S, Rge. 15W, Pratt County, Kansas
 DRILLING STARTED 3-1, 1965; DRILLING COMPLETED 3-15, 1965
 WELL COMPLETED 4-14, 1965; WELL CONNECTED _____, 19____
 ELEVATION: 2022 ft. Ground Level; CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used

RECEIVED
 STATE CORPORATION COMMISSION
 APR 22 1965
 CONSERVATION DIVISION
 Wichita, Kansas

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8-5/8"	355	450	
4-1/2"	4139	185	2200

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Surface sand & soil	0	265			
Red bed	265	780			
Red bed & shale	780	1866			
Lime	1866	2315			
Shale & lime	2315	3865			
Lime	3865	4350			
Total Depth	4350				

RESULTS of INITIAL PRODUCTION TEST: _____