


15-151-20240-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Pratt County, Sec. 3 Twp. 26S Rge. (X) 15 (W)  
Location as "NE/CNW/SW" or footage from lines C SE NW  
Lease Owner Patrick Petroleum Corporation  
Lease Name Neelly Well No. 1  
Office Address 330 Page Court, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 23, 1974  
Application for plugging filed March 23, 1974  
Application for plugging approved March 23, 1974  
Plugging commenced March 23, 1974  
Plugging completed March 23, 1974  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 4441 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				85-7/8"	315'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with 40 sacks cement through drill pipe. Mud in hole to 40 feet, pushed 1/2 sack hulls and plug to 40' mixed 13 sacks cement. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 26 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
3-26-74

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of March, 1974

My commission expires May 9, 1975 Betty Brandt Notary Public.

15-151-20240-0000

ROTARY DRILLERS' LOG

OPERATOR: Patrick Petroleum Corp. DRILLING COMMENCED: March 12, 1974  
 330 Page Court  
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: March 23, 1974  
 505 Union Center  
 Wichita, Kansas 67202

CASING RECORD: 16 Jts. 315' 8-5/8" LOCATION: Neelly No. 1  
 cemented with 300 sacks. C SE NW  
 Section 3-26S-15W  
 Pratt County, Kansas


0 - 230	Sod & sand
230 - 315	Clay
315 - 340	Red bed
340 - 985	Shale & red bed
985 - 1020	Anhydrite
1020 - 1745	Shale & shells
1745 - 1904	Shale & lime
1904 - 2030	Lime & shale
2030 - 2220	Shale & lime
2220 - 2665	Lime
2665 - 2915	Lime & shale
2915 - 2956	Lime
2956 - 3287	Shale & lime
3287 - 3648	Lime
3648 - 3755	Lime & shale
3755 - 3880	Shale
3880 - 4325	Lime
4325 - 4363	Cherty conglomerate
4363 - 4380	Lime & shale
4380 - 4408	Shale
4408 - 4441	Lime & chert
4441	Rotary Total Depth

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 26 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves  
President



Subscribed and sworn to before me, a Notary Public, this 25th of March, 1974.

Betty Brandt  
Betty Brandt Notary Public