

15-151-20184-0600

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

PRATT County. Sec. 10 Twp. 26S Rge. (E) 15(W)

Location as "NE/CNW%SWX" or footage from lines. NE SW SE
Lease Owner U.S. HYDROCARBON
Lease Name NEELY Well No. 8M
Office Address Box 11027, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/14 19 71
Application for plugging filed 11/14 19 71
Application for plugging approved 11/14 19 71
Plugging commenced 11/14 19 71
Plugging completed 11/14 19 71
Reason for abandonment of well or producing formation Dry Hole



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4362 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PWT IN	PULLED OUT
Top soil & sand		0	384	8 5/8	384	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill w/heavy mud to 060'
Set 1st plug at 600' w/30 sx Cem.
Fill w/heavy mud to 350'
Set 2nd Plug w/20 sx cem.
Fill w/heavy mud to 40' w/10 sx.
Bridge rat hole w/2 sx cem.
Compleat @ 2:30 PM 11/14/71

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 Sutton Place, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Gabbert Jones (employee of owner) or ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God. GABBERT-JONES, INC.

(Signature) Jack W. Gabbert, Exec. Vice Pres.
830 Sutton Place
Wichita, Kansas (Address)

Subscribed and sworn to before me this 22 day of November, 19 71

My commission expires Nov. 29, 1971 Marjorie Hall Notary Public.



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

NEELY 8 M
 NE SW SE, Sec. 10-26S-15W
 Pratt County, Kansas

15-151-20184-0000

Commenced: November 3, 1971
 Completed: November 14, 1971

OPERATOR: UNITED STATES HYDROCARBON CO.

Depth		Formation	Remarks
From	To		
0	150	Sand	Ran 18 joints of used 8 5/8" casing
150	330	Sand and shale	Set @ 384' w/265 sks common, 2% Gel,
330	397	Redbed	2% CC, 3% CC last 100 sks.
397	1003	Shale and shells	P.D. 7:45 PM 11/2/71
1003	1019	Anhydrite	Cement Circ. Job by Dowell
1019	1800	Shale and shells	
1800	2200	Shale and lime	
2200	3727	Lime and shale	
3727	3815	Shale and lime	
3815	4035	Lime and shale	
4035	4050	Lime	
4050	4091	Lime and shale	
4091	4348	Lime	
4348	4362	Chert	
4362	TD		Dry and Abandoned

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 19 1971
 CONSERVATION DIVISION
 Wichita, Kansas

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the NE SW SE, Sec. 10-26S-16W, Pratt County, Kansas, to the best of my knowledge and belief.

James S. Sutton II
 James S. Sutton, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 16th day of November, 1971, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
 Marjorie Hall, Notary Public

My commission expires Nov. 29, 1971

