

To: 120514  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

12-27  
API NUMBER 19-047-20,474-0000 283

TECHNICIAN'S PLUGGING REPORT

Operator License # 8791

Operator: El-Kan Exploration  
Name & Address: P.O. Box 105  
Garfield, KS 67529

N/2 NE SE NW SEC. 10, T 26 S, R 16 W/E  
3795 feet from S section line  
2970 feet from E section line

Lease Name Schultz Well # 3 A  
County Edwards 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 460

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Greensburg Well Service License Number 5414

Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 3 p.m. Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2294

Perfs: 4 1/2" at 4495', Perfs at 4384-4406'

1st plug sand back to 4350' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 27 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 600 psi and shut in 100 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
1-4-91  
JAN 4 1991

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3323' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE JAN 22 1991

INV. NO. 30550  
12-27

Signed Duane Rankin  
(TECHNICIAN)