

1-27-88

196 R

To: 1 030910  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,157-0000  
130' E of C  
N/2 NW NW, SEC. 17, T 26 S, R 16 W/EX

4950 feet from S section line  
4490 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5538

Lease Name "RG" Monaghan Well # 1

Operator: Tom Kat Ltd.

County Edwards 154.38

Name & Address: Box 20403

Well Total Depth 4750 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 27 Month: 1 Year: 19 88

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4720' Perfs at 4486-96' Elevation 2073'

1st plug sand back to 4430' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 1400',

3rd plug pump 50 sx cement at 450',

4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4430' and dumped 5 sx cement on top of sand through bailer.

2nd plug spot 15 sx gel and 50 sx cement at 1400',

3rd plug pumped 50 sx cement at 450',

4th plug pumped 10 sx cement at 40-0'.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 29 1988 1-29-88  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED (copy to ~~customer~~) observe this plugging.

DATE 2-4-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 19734