

1 040952

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-21,225 -0000

E/2. SE SE, SEC. 22, T 26 S, R 16 W/E

660 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Salser B Well # 1

Operator: Oil Producers, Inc. of Kansas

County Edwards

Name & Address P.O. Box 8647

Well Total Depth 4535 147.39 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 378

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 3:15 p.m. Day: 12 Month: 4 Year: 1995

Plugging proposal received from Kevin Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4528' w/150 sx cement, PBTD 4503', Perfs at 4450-65'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4 p.m. Day: 12 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4' sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

RECEIVED STATE CORPORATION COMMISSION

APR 18 1995 4-18-95

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2333' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 4-26-95

Signed Stephen J. Penfer (TECHNICIAN)

INV. NO. 42701