

1 090298

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,583-6000

C SE SW, SEC. 23, T 26 S, R 16 W/E

660 feet from N/S section line

3300 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Stegman Well # 2

Operator: Oil Producers, Inc.

County Edwards 145.83

Name & Address P. O. Box 8647

Well Total Depth 4487 feet

Wichita, KS 67208

Conductor Pipe: Size 13 3/8" feet 118

Surface Casing: Size 8 5/8 feet 423

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 6 Month: March Year: 19 85

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4480' PBD 4462' Perfs at 4428-34'

1st plug sand back to 4375' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls

release 8 5/8" rubber plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1985
3-11-85

CONSERVATION DIVISION

Plugging Proposal Received by Robert Tarbutton Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 9:00 am Day: 6 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 550 psi and shut in 250 psi. Used 60/40 Pozmix 2% gel 3% cc by Allied

No. 1836

Remarks: Recovered 2236' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 3-12-85

Signed Robert Tarbutton
(TECHNICIAN)

INV NO. 7320