

10-23

1 040336

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,073-0000

NE NW SE, SEC. 23, T 26 S, R 16 W/E
2310 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Stegman Well # 3

Operator: Oil Producers, Inc. of Kansas
Name & Address Box 8647
Wichita, KS 67208

County Edwards 147.23
Well Total Depth 4530 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 640

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:15 a.m. Day: 23 Month: 10 Year: 1989

Plugging proposal received from Jack Smith

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4528' PBD 4425' Perfs at 4392-95'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 23 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand bridge with bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

OCT 26 1989 10-26-89

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3085.75' of 4 1/2" casing
(If additional description is necessary, use BACK of this report)
Wichita, Kansas

INVOICED

DATE 10-30-89

INV. NO. 26274

Signed Stephen J. Pfeifer (TECHNICIAN)