

To: 1-040734 2-12  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-21;012-0000  
SE NE SW, SEC. 23, T 26 S, R 16 W/E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address  
P.O. Box 8647  
Wichita, KS 67208

Lease Name Wood E Well # 2  
County Edwards 147.38  
Well Total Depth 4535 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 490

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635  
Address P.O. Box 251, Great Bend, KS 67530

Company to plug at: Hour: 9:30 a.m. Day: 12 Month: 2 Year: 19 93

Plugging proposal received from Gary Burke  
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4531' w/150 sx cement, PBTD 4503', Perfs at 4478-88, 4420-26, 4409-14'  
1st plug sand back to 4360' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 125. sx cement.

KANSAS RECEIVED  
CORPORATION COMMISSION  
2-17-93  
Fispeye Pfeifer  
(TECHNICIAN)  
CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_  
Operations Completed: Hour: 10:30 a.m. Day: 12 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4360' and dumped 4 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Maximum pressure 50 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2713' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

INVOICED  
DATE 2-19-93  
WV. NO. 37996  
2-12

Signed Stephan J. Pfeifer  
(TECHNICIAN)