

To: <sup>1</sup> 120896  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

2-24

API NUMBER 15- 047-~~21,067~~-<sup>21062</sup>0000  
SW SW SW , SEC. 23 , T 26 S, R 16 W/E  
330 feet from S section line  
4950 feet from E section line  
Lease Name Wood E Well # 3  
County Edwards  
Well Total Depth 4549 147.84 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 517

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address P.O. Box 8647  
Wichita, KS 67208

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 1:30 p.m. Day: 24 Month: 2 Year: 19 94

Plugging proposal received from Joe Strube  
(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361

vers: 4 1/2" at 4549' w/150 sx cement, PBSD 4543', Perfs at 4466-4516' (4 sets)  
1st plug sand back to 4415' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper  
plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back 4 1/2" casing to 4415' and dumped 4 sx cement on  
top of sand through bailer,  
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.  
Pumping pressure 0-300 psi and shut in 50 psi.

3-2-94

RECEIVED  
STATE CORPORATION COMM

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2223' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form)

MAR 02 1994

INVOICED observe this plugging.

DATE MAR 02 1994

Signed Dennis Reber  
(TECHNICIAN) CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 40081