

1 120893

2-24

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,266-0000  
W/2 W/2 SW, SEC. 23, T. 7, S. 26, R. 16 W/2

1320 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Wood E. Well # 4

Operator: Oil Producers, Inc. of Kansas

County Edwards

Name & Address P.O. Box 8647

Well Total Depth 4500 146.25 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 382

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 12 p.m. Day: 24 Month: 2 Year: 19 94

Plugging proposal received from Joe Strube

(company name) DS&W Well Servicing, Inc. (phone) 316-672-6373

vers: 4 1/2" at 4499' w/125 sx cement, PBD 4465', Perfs at 4422-37'

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 24 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4370' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-300 psi and shut in 100 psi.

3-2-94

RECEIVED

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2308' of 4 1/2" casing. (If additional description is necessary, use BACK of this form)

Hold / observe this plugging.

INVOICED

Signed [Signature] CONSERVATION DIVISION Wichita, Kansas (TECHNICIAN)

DATE MAR 08 1994

WV. NO. 40080