

120960

8-24

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,839-0000
NW NW SE, SEC. 11, T. 26 S, R. 16 W
2310 feet from S section 11
2310 feet from E section 11

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name:
Address: 1560 Broadway, Ste. 1900
Denver, CO 80202

Lease Name Schultz J Well # 2-11
County Edwards
Well Total Depth 4463 145.05
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 466

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Benson Mineral Group, Inc. License Number 5817
Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9 a.m. Day: 24 Month: 8 Year: 19 94
Plugging proposal received from Phillip Kempton
(company name) Benson Mineral Group, Inc. (phone) 303-863-3500

vers: 4 1/2" at 4462' w/350 sx cement, PBTD 4462', Perfs at 4380-98', 4404-20'
1st plug sand back to 4320' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 24 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4320' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs., and 150 sx cement.
Pumping pressure 0-750 psi and shut in 200 psi.

RECEIVED STATE CORPORATION COMMISSION
8-31-94

Remarks: Used common cement w/2% gel by BMG. Recovered 1900' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED

DATE SEP 12 1994
INV. NO. 41182

Signed Duane Rankin (TECHNICIAN)

AUG 31 1994
STATE CORPORATION COMMISSION
WICHITA, KANSAS