

10-20-88

API NUMBER 15-047-20,858-0000

To: 1 061147  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW NW NE, SEC. 11, T 26 S, R 16 W EX

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Wood Well # B 1

Operator: Oil Producers Inc. of Kansas

County Edwards 145.21

Name & Address Box 8647

Well Total Depth 4468 feet

Wichita, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 450

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 20 Month: 10 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4467' PBD 4459' Perfs at 4398-4418'

1st plug sand back to 4350' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1988

10-24-88

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:40 a.m. Day: 20 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Maximum pressure 500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2466' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED

(if possible) observe this plugging.

DATE 10-28-88

Signed Paul A. Luthi  
(TECHNICIAN)

INV. NO. 22836