

1 051229

11-2

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,315-6660

C NW NW, SEC. 11, T 26 S, R 16 W/E

4620 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Salser Well # 1

Operator: Benson Mineral Group, Inc.

County Edwards 146.74

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 4515 feet

Golden, CO 80401

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 2 Month: 11 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4500' PBDT 4448' Perfs at 4372-4400'

1st plug sand back to 4320' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
11-6-89 STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Pfeifer NOV - 6 1989  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operations Completed: Hour: 2 p.m. Day: 2 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4320' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2020' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-13-89

Signed Richard W. Leary  
(TECHNICIAN)

INV. NO. 26380