

To: 1 040877  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-15

API NUMBER 15-047-20,714-0950

NE NE SW, SEC. 11, 7 26 S, R 16 W.  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Schultz T Well # 1-11

Operator: Benson Mineral Group, Inc.

County Edwards

Name & Address 1560 Broadway, Ste. 1900

Well Total Depth 4514 146.71 feet

Denver, CO 80202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Benson Mineral Group, Inc. License Number 5817

Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 9:30 a.m. Day: 15 Month: 8 Year: 19 94

Plugging proposal received from Phillip Kempton

(company name) Benson Mineral Group, Inc. (phone) 913-762-3551

vers: 4 1/2" at 4514' w/200 sx cement, PBTD 4508', Perfs at 4380-4400'

1st plug sand back to 4300' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:45 a.m. Day: 15 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 100 psi and shut in 50 psi.

8-17-94

Remarks: Used Class A cement w/2% gel by BMG. Recovered 1860' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form)

(and/or supervisor) observe this plugging.

**INVOICED**

DATE AUG 29 1994

INV. NO. 41061

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 17 1994  
WICHITA, KANSAS