

To: 1 051230
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-2
15-047-20712-0003 37
API NUMBER 15 Docket # D-20,143
NE NW NW, SEC. 14, T 26 S, R 16 W/E
4950 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name & Address 1536 Cole Blvd., Suite 220
Golden, CO 80401

Lease Name Schultz G Well # 1-14 SWD
County Edwards 177.68
Well Total Depth 5467 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8 a.m. Day: 26 Month: 10 Year: 19 89

Plugging proposal received from Bill Philo
(company name) Benson Mineral Group, Inc. (phone) 303-232-0100

were: 4 1/2" at 5466' w/260 sx cement, 2 3/8" tubing at 3998', Packer @ 3898'
Dvd at 4116' w/75 sx cement, Perfs at 4404-5384' (5 sets)

1st plug pump 50 sx cement through 2 3/8" fiberglass tubing at 3800', lay down one joint,
2nd plug pump 25 sx cement at 3765'.

RECEIVED
STATE CORPORATION COMMISSION
11-6-89 NOV - 6 1989

Plugging Proposal Received by Steve Pfeiffer
(TECHNICIAN)
Conservation Division
Wichita, Kansas

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 2 Month: 11 Year: 19 89
Duane Rankin witnessed:

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement through 2 3/8" fiberglass tubing, shot
tubing at 3800', layed down one joint, 2nd plug pumped 25 sx cement at 3765', shot 4 1/2"
casing at 2120' and layed down one joint, 3rd plug pumped 50 sx cement at 2080'-10/26/89.
11/2/89-Richard Lacey witnessed: 4th plug pumped 4 sx hulls, 10 sx gel, 50 sx cement,
10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement down 8 5/8".

Maximum pressure 300 psi and shut in 50 psi. Packer & 200' of 2 3/8" tubing left in 4 1/2".
Used common cement on bottom plug and 60/40 Pozmix 6% gel on top plugs by Allied.
Remarks Recovered 2120' of 4 1/2" casing and 3765' of 2 3/8" fiberglass tubing.
(If additional description is necessary, use BACK of this form.)

INVOICED
with 11-7-89 observe this plugging.

DATE 11-7-89
INV. NO. 26367
11-2

Signed Richard W. Lacey
(TECHNICIAN)