

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21436-00-00
Spot: CSENE Sec/Twnshp/Rge: 15-26S-16W
3300 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: SCHULTZ Well Number: 1
County: EDWARDS Total Vertical Depth: 4500 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/4 25
Surface Casing: Size 8.625 feet: 463 WITH 260 SX CMT
Production: Size 4.5 feet: 4499 WITH 140 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2002 1:15 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal: Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4340' & 4 SX CMT. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/02/2002 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4439'. PERFS AT 4391-97 & 4410-30'. SANDED BACK TO 4340' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH SUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 490' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

MAY 07 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2620' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED MAY 06 2002

DATE 5-7-02

TEL. NO. 2022061750 MP

Forklift