

To: 1 040714
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corporation

Name:

Address P.O. Box 723

Hays, KS 67601

API NUMBER 15- 047-20,230-0000 3 & ✓ R

E/2 SE SW, SEC. 12, T 26 S, R 16 W

660 feet from S section line

2970 feet from E section line

Lease Name Bevan Wood Well # 1

County Edwards 14658

Well Total Depth 4510 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124-0847

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 10 Year: 1992

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

Work: 4 1/2" at 4509' w/150 sx cement, Perfs at 4350-4400'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper

plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 27 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 250 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 1965.6' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did) observe this plugging.

DATE 11-13-92

WELL NO. 36742

Signed (TECHNICIAN)