

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

7-23

2-070778

API Number: 15-155-21,422-0000

CSH NE NW SECTION 15 TWP 26 RANGE 09W

OPERATOR LICENSE # 31191  
OPERATOR R&B OIL AND GAS, INC.  
NAME & 904 N. LOGAN  
ADDRESS ATTICA, KS 67009

990 FEET FROM SECTION LINE  
3300 FEET FROM E SECTION LINE

LEASE NAME LAWSON #2  
COUNTY RENO  
WELL TOTAL DEPTH 4300' 139.79  
PIPE 5 1/2" @ 4249  
SURFACE CASING 8 5/8" @ 296'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 23 MONTH: 7 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: \_\_\_\_\_

COMPANY NAME: R&B OIL PHONE: (316) 254-7972

WERE: CIBP - 3050'  
2850' - 50 SACKS  
1300' - 35 SACKS  
800' - 35 SACKS  
300' TO 0

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL  PART  NONE

COMPLETED: HOUR: 12:30 DAY: 23 MONTH: 7 YEAR: 1998

ACTUAL PLUGGING REPORT: SET CIB PLUG AT 3050', SHOT 5 1/2" CASING OFF AT 2850' AND PUMPED 50 SACKS  
PULLED TO 1300'. PUMPED 35 SACKS. PULLED TO 300' CIRCULATED CEMENT TO BOTTOM.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 27 1998

REMARKS: ALLIED #5803 60/40 POZ, 4% GEL

7-27-98  
CONSERVATION DIVISION  
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

*Jack Luthi*  
JACK LUTHI

FORM CP-2/3  
REV. 3/90

INVOICED

DATE JUL 30 1998

INV. NO. 57056

7-23