

2-070747

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

11-3

API NUMBER: 15-155-21,173-0000

C NE NW, SECTION 15 TOWNSHIP 26 RANGE 9W

OPERATOR LICENSE # 31191 4620 FEET FROM S SECTION LINE

OPERATOR R & B OIL & GAS INC 3300 FEET FROM E SECTION LINE

NAME & 904 NORTH LOGAN

ADDRESS ATTICA, KS 67009

LEASE NAME: LAWSON #1-15

COUNTY: RENO 139.91

WELL TOTAL DEPTH: 4305'

PIPE: 5 1/2" @ 4302'

SURFACE CASING: 8 5/8" @ 320'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: P.O. BOX 333, ATTICA, KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 3 MONTH: 11 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JERRY

COMPANY NAME: SHAWNEE WELL SERVICE PHONE: (316) 254-7893

WERE: CIBP AT 4100', 2 SACKS OF COMMON

35 SACKS AT 1300'

35 SACKS AT 800'

370' TO SURFACE

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 19 1997
11-19-97

CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 4:00PM DAY: 3 MONTH: 11 YEAR: 1997

ACTUAL PLUGGING REPORT: SET CIBP AT 4100' AND 2 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 1500'. PULLED TO 1300', PUMPED 35 SACKS. PULLED TO 800', PUMPED 35 SACKS. PULLED TO 370', PUMPED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED

INVOICED

DATE 11-24-97

INV. NO. 495-199

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI