

2-010162

7-21

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-155-21,417-0000

SE NW SW, SECTION 15 TOWNSHIP 26 RANGE 9W

OPERATOR LICENSE # 31191 1650 FEET FROM S SECTION LINE  
OPERATOR R & B OIL & GAS INC 4290 FEET FROM E SECTION LINE  
NAME & P.O. BOX 195  
ADDRESS ATTICA, KS 67009-0195  
LEASE NAME: BEAT #2  
COUNTY: RENO  
WELL TOTAL DEPTH: 4168' 135.46  
PIPE:  
SURFACE CASING: 8 5/8" @ 289'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: DUKE DRILLING COMPANY INC

ADDRESS: 310 WEST CENTRAL, SUITE 117, WICHITA, KS 67202 LICENSE: 5259

COMPANY TO PLUG AT: HOUR: 20:00 DAY: 21 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JOHN ARMBRUSTER

COMPANY NAME: DUKE DRILLING COMPANY PHONE: (316) 267-1331

WERE: FILL HOLE WITH HEAVY MUD AND SPOT PLUGS THROUGH DRILL PIPE. PULL PIPE TO 1300' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 800' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 339' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 60' AND SPOT 25 SACKS OF CEMENT. FILL RATHOLE WITH 20 SACKS OF CEMENT AND MOUSEHOLE WITH 15 SACKS OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY: DISTRICT II

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( ) PART ( ) NONE (  )

COMPLETED: HOUR: 21:45 DAY: 21 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: FILLED HOLE WITH HEAVY MUD. SPOTTED PLUGS THROUGH DRILL PIPE. SPOTTED 35 SACKS OF CEMENT AT 1300', SPOTTED 35 SACKS OF CEMENT AT 800', SPOTTED 35 SACKS OF CEMENT AT 339', AND SPOTTED 25 OF CEMENT AT 60'. FILLED RATHOLE WITH 20 SACKS OF CEMENT AND MOUSEHOLE WITH 15 SACKS OF CEMENT.

REMARKS: 60/40 POZ 4% GEL ALLIED #6267

I DID NOT OBSERVE THIS PLUGGING.

*Michael R. Wilson*

MICHAEL R. WILSON

RECEIVED  
KANSAS CORPORATION COMMISSION

FORM CP-2/3  
REV. 3/90

AUG 12 1997

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 8-13-97

INV. NO. 48785

SEP 22 1997-21