

2 100540

10-25

15-155-19114-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-21,734 95-129C

SE, SEC. 20, T 26 S, R 9 WXR

1340 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9533

Lease Name Shirley Woodson # 1

Operator: Fairchild Exploration

County Reno 137.48

Name & Address RR #3

Well Total Depth 4230 feet

Kingman, KS 67068

XXXXXXXXXX Pipe: Size 5-1/2 feet 4230'/100 sx

316-532-3047

Surface Casing: Size 8-5/8 feet 230'/150 sx

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated perf. 4196'

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00p Day: 25 Month: 10 Year: 19 89

Plugging proposal received from Vernon Dunce

(company name) Kelso Casing Pulling (phone)

were: Sand 50' above top perf 5 sx cmt - shoot & pull pipe - circulate thru pipe
25 sx cmt at 1350' - pull pipe to 860' & circ 25 sx - pull pipe to 280' &
circ cement to surface.

Plugging Proposal Received by Phil Worley (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30p Day: 25 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT Sanded to 4140' and dumped 5 sx cement w/bailer - shot

and pulled 3029' of 5-1/2" to 1350' - circulated 25 sx cement - pulled pipe to 860'

and circ 25 sx cement - pulled pipe to 280' and circ 90 sx to surface - topped

off after pipe was pulled out.

Remarks: Allied #6126 60/40 4% gel

(If additional description is necessary, use BACK of this form) State of Kansas

I (and XXXXXXXX) observe this plugging.

DATE 11-3-89 WK

Signed P.L. Sanders (TECHNICIAN)

INV. NO. 26346