

1 090456

8-22

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,418-6000
SE SE SE, SEC. 4, 7 26 S, R 16 W,
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9449
Operator: Great Eastern Energy
Name & Address: 672 W. 4th
Hoisington, KS 67544

Lease Name Parker Well # 1
County Edwards 143.00
Well Total Depth 4400 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 394

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 22 Month: 8 Year: 19 94

Plugging proposal received from Bill Reed
(company name) Great Eastern Energy (phone) 316-653-2277

Work: 5 1/2" at 4397' w/125 sx cement, Open hole 4397-4400'
1st plug sand back to 4347' and dump 5 sx cement on top of sand through bailer.
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4347' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 150 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(State) (License) observe this plugging.

DATE AUG 29 1994

INV. NO. 41077

Signed [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1994

CONSERVATION DIVISION
WICHITA, KANSAS