

To: 1 120498
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

11-29
API NUMBER 15-047-20,578-0060
SE NE SW, SEC. 4, T 26 S, R 16 W/E
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers Inc. of Kansas
Name & Address P.O. Box 8647
Wichita, KS 67208

Lease Name Parker Well # A-1
County Edwards
Well Total Depth 4460 144.95 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 479

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 29 Month: 11 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4458' w/150 sx cement, PBTD 4450', Perfs at 4403-07, 4416-28'
1st plug sand 4 1/2" casing back to 4350' and dump 4 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
12-6-90
DEC 6 1990
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Duane Rankin

Plugging Operations attended by Agent?: All Part _____

Operations Completed: Hour: 10 a.m. Day: 29 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4350' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2401' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 12-10-90
INV. NO. 30204

Signed Duane Rankin
(TECHNICIAN)