

To: 1 040582
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-2.2 API NUMBER 15- 047-20,471-0000 246

SE SW SE, SEC. 4, T. 26 S, R. 16 W/16
330 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5992
Operator: Patton Oil Company
Name & Address 672 W. 4th St.
Hoisington, KS 67554

Lease Name Parker Well # 3
County Edwards 144.13
Well Total Depth 4435 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 22 Month: 10 Year: 19 91

Plugging proposal received from Bill Reed
(company name) Patton Oil Company (phone) 316-653-2277

were: 5 1/2" at 4423' w/125 sx cement, PBSD 4150', Perfs at 4069-75'
1st plug sand back to 4015' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 22 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4019' and dumped 5 sx cement on top of sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.
Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2247' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)
STATE CORPORATION COMMISSION

INVOICED
DATE 11-14-91 33709
OCT 29 1991 signed Stephen J. Pfeifer
(TECHNICIAN)
CONSERVATION DIVISION
Wichita Kansas