


WELL PLUGGING RECORD

5-047-00299-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Edwards County. Sec. 13 Twp. 26 Rge. 16 (X) (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Ambassador Oil Corporation
Lease Name Elmer D. Wood 'A' Well No. 1
Office Address Box 9338, Fort Worth 7, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 4-22-56 19
Application for plugging filed 4-22-56 19
Application for plugging approved 4-22-56 19
Plugging commenced 4-22-56 19
Plugging completed 4-22-56 19
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4695 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	9 joints of 8-5/8" (288.87) set @ 296' w/ 2% Gel., 600# C.C.				275 sacks common,	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud, mixed 50 sacks cement and pumped plug down with same. P.D. 1:45 a.m. 4-22-56 Squeezed by Globe Cementing Co. under 225# pressure with a standing pressure of 50#.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1956
CONSERVATION DIVISION
Wichita, Kansas

5-10-56


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Garvey Drilling Company
Address 311 East Third, Wichita, Kansas

STATE OF TEXAS, COUNTY OF TARRANT, ss.
Ambassador Oil Corporation (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. S. Young Jr. Chief Prod. Clerk
3101 Winthrop, Fort Worth, Texas (Address)

SUBSCRIBED AND SWORN to before me this 22 day of April, 19 56

My commission expires June 1, 1957
Robert G. Gierck Notary Public.



PLUGGING
FILE SEC 13 T 26 R 16W
BOOK PAGE 56 LINE 7

WELL LOG

File Copy

COMPANY **AMBASSADOR OIL CORPORATION**

SEC. **13 T. 26 R. 16W**

FARM **Elmer D. Wood 'A' NO. 1**

LOC. **SW NW NW**
15-647-00299-0000

TOTAL DEPTH **4695'**

COUNTY **Edwards Co., Kansas**

COMM. **April 7, 1956** COMP. **April 22, 1956**



CONTRACTOR **GARVEY DRILLING COMPANY**

CASING **8-5/8" @ 296' w/275 sacks**

ELEVATION **2065 D.F.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

249	Sand, Gravel & Shale Streaks
297	B. Shale, Shells & Red Bed
1020	Red Bed
1066	Anhydrite
1230	Shale
2010	Shale & Shells
2140	Shale & Lime
2420	Lime
2685	Lime & Shale
2875	Shale & Shells
3885	Shale & Lime
4285	Lime
4382	Lime & Shale
4450	Chert
4486	Sand
4532	Chert
4595	Chert & Lime
4610	Lime & Shale
4645	Shale
4686	Lime
4695	Arbuckle
4695	T.D.

RECEIVED
STATE CORPORATION COMMISSION
MAY 10 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 13 T 26 R 16W
BOOK PAGE 56 LINE 7

State of KANSAS }
County of SEDGWICK }

I, Carl Hurty of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the Elmer D. Wood A #1 well

Carl Hurty

Subscribed and sworn to before me this 25th day of April 19 56

My Commission Expires: July 8, 1958

D. M. Kennedy
NOTARY PUBLIC