

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

RECEIVED Form CP-4
 STATE CORPORATION COMMISSION 15-80

MAR 7 1983

CONSERVATION DIVISION
 Wichita, Kansas

WELL PLUGGING RECORD
 15-847-20210-0000

Give All Information Completely
 Make Required Affidavit

COUNTY Edwards SEC. 13 TWP. 26s RGE. 16w E/W
 Location as in quarters or footage from lines:
SE NW

Locate Well
 correctly on above
 Section Platt.

Lease Owner Beren Corporation
 Lease Name Grizzel-Wood #1 Well No. _____
 Office Address 970 Fourth Financial Center, Wichita, Ks. 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 2/14/83
 Plugging completed 2/22/83
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation _____ Depth to top _____ bottom T.D. 4510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	435'	none
				4 1/2"	4509'	2304'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Pumped bottom with 35 sacks cement & 1 hull to 3800'. Shot well at
3020', 2806', 2613', 2523', 2416', & 2304'. Pulled total of 74 joints.
Plugged well with 2 sacks hulls, 15 gel, 70 cement, 10 gel, plug, &
130 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 1983

My Commission expires:



Irene Hoover
 Notary Public.

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-047-70270-6000

WELL LOG ----- GRIZZELL-WOOD #1
Located: SE NW, Section 13-26S-16W, Edwards County,
Kansas

OWNER: Beren Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 18, 1977
COMPLETED: January 1, 1978

TOTAL DEPTH: 4510'

<u>Log</u>	<u>Casing Record</u>
0 - 300 Sand and Shale	Ran 10 joints used 28#, 8 5/8" casing, 324.67' set at 435' K.B. with 300 sacks 60/40 Pozmix with 3% cc. Plug down at 8:15 Pm, 12-18-77, by Allied Cement.
300 - 438 Shale	
438 - 690 Shale, Sand and Red Bed	
690 - 1047 Red Beds	
1047 - 1065 Anhydrite	
1065 - 1735 Shale and Sand - Salt and Lime	
1735 - 3874 Shale and Lime	
3874 - 3910 Shale	
3910 - 3960 Lime and Shale	
3960 - 4166 Lime	
4166 - 4357 Lime, Chert, Shale	
4357 - 4386 Cherty Lime and Shale, Sand and Chert	
4386 - 4510 Chert and Lime	Ran 142 joints 4 1/2" OD casing, 4515' cemented at 4509' K.B. with 50 sacks 50/50 Pozmix, 10# gilsonite per sack, followed with 250 sacks 60/40 Pozmix, 18% salt, 10# gilsonite. Plug down at 6:00 PM, 1-1-78.

RECEIVED
STATE CONSERVATION COMMISSION

NOV 09 1982

CONSERVATION DIVISION
Wichita, Kansas