


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Edwards County, Sec. ¹⁵~~22~~ Twp. 26 Rge. 16 (XX) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Wichita Iron & Metals Corp., Inc.
Lease Name SALSER Well No. 1
Office Address Box 13021, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas and Oil
Date well completed 8-21 19 58
Application for plugging filed 7-22 19 66
Application for plugging approved 7-22 19 66
Plugging commenced 7-30 19 66
Plugging completed 8-6 19 66
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 5-30 19 66
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Kinderhook Depth to top _____ Bottom _____ Total Depth of Well 4483 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	408'	None
				5-1/2	4483'	2333'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand from 4483' to 4400'. Ran 5 sacks of cement from 4400' to 4370'. Mudded from 4370' to 400'. Rock bridge from 400' to 390'. Ran 5 sacks of cement from 390' to 375'.

Bailed out water and ran 20 sacks of cement from 375' to 310'. Mudded from 310' to 35'. Rock and 10 sacks of cement from 35' to base of cellar.

RECEIVED
AUG 26 1966
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 156, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Ray Stekoll (~~employee~~ owner) or (~~owner~~ operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Wichita Iron & Metals Corp., Inc.
(Signature) By: Ray Stekoll
Box 13021, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 66
Evelyn V. North
Evelyn V. North Notary Public.
My commission expires December 22, 1966

15-047-60067-000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company- L. C. SMITHERMAN -OIL PRODUCER
Farm- Salzer No. 1

SEC. 15 T. 26 R. 16W
SE SE SE

Total Depth. 4483'
Comm. 8/1/58 Comp. 8/21/58
Shot or Treated.

County Edwards
KANSAS

Contractor. L. C. Smitherman Drilling Co.
Issued. 5/21/60



CASING:
8 5/8" 408' w/250 sks.
5 1/2" 4483' w/125 sks.

Elevation. 2071 GL

Production. 30 BOPD & 1,000,000
CFG

Figures Indicate Bottom of Formations.

sand	200
shale	408
red bed & shale	1108
shale	2066
lime	2230
lime & shale	2380
lime & shale streaks	2490
shale & lime	2890
shale	3060
shale & lime	3544
lime	3772
lime & shale	3900
Brown lime	3922
Kansas City lime	3954
lime	3991
lime & shale	4346
lime & sand	4394
sand	4410
sand & chert	4421
shale & chert	4462
cherty lime & sand	4483
Total Depth	

TOPS: SCOUT	
Heebner	3758
Toronto	3774
Brown lime	3902
Lansing	3922
Base Kansas City	4184
Cherokee	4383
Kinderhook sand	4392
Viola	4476

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1966
CONSERVATION DIVISION
Wichita, Kansas