


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittig Building  
Wichita, Kansas

Edwards County. Sec. 15 Twp. 26 Rge. 16 (E) (W)

NORTH



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines \_\_\_\_\_

Lease Owner \_\_\_\_\_

Lease Name Wood Well No. 1

Office Address \_\_\_\_\_

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-16-58 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved 12-16 19 58

Plugging commenced 12-16 19 58

Plugging completed 12-16 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot (Frank)

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4538 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	365'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole to 245' with heavy mud

Set Wood plug - 1/3 sx hulls and 20 sx Cement through the Drill pipe.

Finished filling hole with mud to 35' below base of cellar -

Set Wood plug 1/3 sx hulls and 10 sx cement

Cement come to bottom of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1959  
CONSERVATION DIVISION  
2-26-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ari-Kan Drilling Company

Address P.O. Box 162 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. F. W. Smith

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. W. Smith

P.O. Box 162 - Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 19 59

Wanda Nichols  
Notary Public.

My commission expires April 1, 1959

PLUGGING  
FILE SEC 15 T 26 R 16W  
BOOK PAGE 9 LINE 11

15-047-00070-0000

Company - Clark Knight Drilling Co., Inc.

Sec. 15-26S-16W  
NW SE NW

Farm - Wood No. 1.

County - Edwards

Total Depth - 4,538'

Elevation: 2075' RB

Comm: 12-2-58 Comp: 12-16-58

Casing: 8 5/8" Cemented at 365'/260 sacks.

Figures indicate Bottom of Formations

Sand and Clay	200	
Pea Gravel	240	
Shale	290	
Sand	300	
Shale	365	Shale and Red Bed 645
Red Bed	720	
Sand and Red Bed	740	
Red Bed	955	
Sand	985	
Red Bed and Sand	1085	
Anhydrite	1095	
Shale and Shells	1200	
Shale and Shells	1510	
Shale	1895	
Shale and Lime	2135	
Lime and Shale	2255	
Lime	2315	
Lime	2395	
Lime and shale	2515	
Lime	2560	
Shale and Lime	2585	
Lime and Shale	2730	
Shale and shells	2750	
Shale and Lime	2980	
Lime and Shale	3105	
Shale and Lime	3205	
Lime and Shale	3475	
Lime	3587	
Shale and Lime	3680	
Lime	3795	
Lime and shale	3900	
Lime and shale streaks	3970	
Lime	4024	
Lime and Shale	4035	
Lime	4427	
Lime shale and Sand	4465	
Lime	4490	
Sandy Lime Kinderhook	4528	
Lime and Chert	4538'	
T. D.	4538'	

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1959

DIVISION