

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD 15-15519104-0000

Reno County, Sec. I4 Twp. 26 Rge. 9 W (E) (W)

Location as "NE/CNW/SW" or footage from lines C N/2 NW SW

Lease Owner Messman & Rinehart Oil Co.

Lease Name Murphy Well No. I

Office Address 1432 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas #117

Date well completed \_\_\_\_\_ 1965

Application for plugging filed Oct 1965

Application for plugging approved Oct 1965


Plugging commenced Oct 16 1965

Plugging completed Oct 20 1965

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 1965

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3892' Feet

Show depth and thickness of all water, oil and gas formations. 3884

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>5 (4 1/8")</u>		<u>3,039'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom of hole with rock. Rock from 3892' to 3870'. Dumped 3 sx of cement, Mudded hole to 220'. Made 10' of rock bridge. Dumped 22 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the celler.

RECEIVED  
STATE CORPORATION COMMISSION

UCT 28 1965

CONSERVATION DIVISION  
Wichita, Kansas

10-28-65

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.  
Address 2809 King St. Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King St. Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 20 th day of October, 19 65

My commission expires January 5, 1965

Judy Lamb  
Notary Public.

NO. 1 MURPHY

15-155-19104-0000

Well Record

Location: Ctr. N/2 NW/4 SW/4  
Section 14-26S-9W  
Reno County, Kansas

Operator: Messman-Rinehart Oil Company  
518 Petroleum Building  
Wichita, Kansas

Contractor: Messman-Rinehart Oil Company  
518 Petroleum Building  
Wichita, Kansas

Casing Record: 8-5/8" @ 220' w/165 sx. cas., 3 gal. 3 c.c.  
5-1/2" @ 3882' w/125 sx. cas., 2 gal.

Commenced: October 8, 1958  
Completed: October 19, 1958  
(rotary)  
Elevation: 1675' K/B  
Production: Gas

\*\*\* LOG \*\*\*

Clay and Sand	105
Red Bed	220
Red Bed, shale & shells	500
Shale & shells	1212
Anhydrite	1252
Shale & Shells	1350
Lime & Shale	1665
Lime	1825
Lime	1955
Lime & Shale	2520
Shale & Lime	2655
Lime & Shale	3388
Lime	3715
Lime & Shale	3879
Mississippi Chert	3884 R.T.D.

Sample Tops

3305' - Brown Lime (-1630)  
3343' - Lansing (-1668)  
3879' - Mississippi "Chert" (-2204)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1965  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

MESSMAN-RINEHART OIL COMPANY

By: \_\_\_\_\_

*J. A. Gilliland*  
J. A. Gilliland

Subscribed and sworn to before me  
this 19th day of November, 1958

*Barbara J. Scott*  
Barbara J. Scott, Notary Public

My Commission Expires: December 1, 1960

COMPLETION DATA

No. 1 Murphy  
Ctr. N/2 NW/4 SW/4  
Section 14-26S-9A  
Reno County, Kansas

- 10-23-58 - Moved in cable tools
- 10-24-58 - Drilled out cement, drilled plug to 3886 ft.  
Making 200,00 cfg natural
- 10-25-58 - Treated with 300 gal. acid, Ran 2" tubing, and Fraced with  
3000 gal. geo-frac and 2500# sand  
Swabbing back load - Total load 664 bbls.  
Making approx. 480,000 cfg and .6 BWPH
- 11-4-58 - Swabbing load - Making approx. 750,000 cfg and 1 1/2 BWPH
- 11/4-11/7 - Blow well 4 hrs./day - Making approx. 6.68 BW
- 11-8-58 - Shut in
- 11-9-58 - Blow well 4 hrs. - Making 2.5 BW  
Gauged 1,100,000 cfg at end of 4 hrs.
- 11-9-58 - Shut in for connection

RECEIVED  
STATE CORPORATION  
NOV 2 1965  
CONSERVATION DIVISION  
Wichita, Kansas