

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
of formations.

Reno County County. Sec. 15 Twp. 26 Rge. 9# (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines Southwest Corner SW/4

Lease Owner Sheffer Drilling Company

Lease Name Fluke Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed August 10 19 48

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced December 23 19 48

Plugging completed January 6 19 49

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

R. Durkee

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 3545 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	285	none
				5 1/2"	3529	2003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with sand to 3529 and cement to 3495--5 sacks cement used

Fill with mud to 250' and cement to 210'--15 sacks cement used

Fill with mud to 15' and cement to cellar--5 sacks cement used

RECEIVED  
CONSERVATION DIVISION  
JAN 22 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

1-22-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mallard Drilling Company  
Address 1016 Union National Bank, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
C. G. Nelson, partner (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. G. Nelson

(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January 19 49

Raywell Wright  
Notary Public.

My commission expires 12/4/59

PLUGGING  
FILE SEC 15 T 26 R 9 W  
BOOK PAGE 75 LINE 41

SHEPPER DRILLING COMPANY

Ft. # 1

Total Depth - - - - - 3533'  
 Comm. - - - - - 7-25-48  
 Comp. - - - - - 9-10-48  
 Contractor - - - - - Sheffer Drilling Company

Sec. 15, Twp. 26, Ra. 9W  
 Reno County, Kansas

Casing

8-5/8" 287'  
 5-1/2" 3529' - 505'

Clay	0-51
Sand	51-135
Shale & Shale	135-145
Red Shale & Shell	145-165
Red Rock	165-281
Redbed & Green Shale	281-700
Shale & Shell	700-875
Salt & Shale	875-920
Shale & Shell	920-1290
Lime & Shale	1290-1306
Shale & Shell	1306-1381
Bro. Lime	1381-1420
Rock	1420-1431
Lime	1431-1495
Lime & Shale	1495-1506
Shale	1506-1535
Lime & Shale	1535-1665
Sand	1665-1690
Lime & Shale	1690-1720
Lime	1720-1795
Lime & Shale	1795-2425
Lime (hard)	2425-2434
Shale & Lime	2434-2520
Chert & Lime	2520-2525
Shale & Lime	2525-2901
Lime & Sandy Gypsum	2901-3005
Lime Hard	3005-3035
Lime & Shale	3035-3052
Shale (stickey)	3052-3080
Lime & Shale	3080-3091
Lime	3091-3110
Lime & Shale	3110-3368
K.C. Lime	3368-3413
Lime	3413-3533

~~354 3529~~  
~~1554 280~~  
~~54 7/2~~

SHEPPER DRILLING COMPANY

By [Signature]  
 Partner

RECORDED  
 DEC 2 1948  
 STATE COMMISSION  
 TRANSPORTATION  
 Top K.C.  
 T.D.

Subscribed and sworn to before me, this 27th day of August 1948.

My Commission Expires My commission expires Dec. 15, 1951

County Sedgewick Notary Public [Signature]

**PLUGGING**  
 FILE SEC 15 T 26 R 9W  
 BOOK PAGE 75 LINE 41