

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 15 Twp. 26 Rge. (E) 9 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 330' from E, 330' from S

Lease Owner The Ohio Oil Company

Lease Name W C Lawson Well No. 1

Office Address McPherson, Kansas.

Character of Well (Completed as Oil, Gas or Dry Hole) Oil

Date, well completed December 3, 193 6

Application for plugging filed 193

Application for plugging approved September 9, 193 8

Plugging Commenced October 5, 193 8

Plugging Completed October 13, 193 8

Reason for abandonment of well or producing formation Encroachment of salt water
and inability to make 1/6% allowable

If a producing well is abandoned, date of last production August 22, 193 8

Was permission obtained from the Conservation Division or its agents before plugging was commenced?
Yes

Name of Conservation Agent who supervised plugging of this well Guy Wiershing

Producing formation Viola Lime Depth to top 4147 Bottom 4149 Total Depth of Well 4149 Feet.

Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Viola Lime	Oil & Water	0	333	12 1/2	336	None
		0	4147	7	4182	1577'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cement at bottom of hole from 4149' to 4130. Filled with heavy mud between plugs from 4130 to top of ground. Set wooden plug, rock and 15' of cement at bottom of surface pipe at 340'. Put rock and 10' of cement below base of cellar. The cement was put in with dump bailer except that at base of cellar. The mud and rocks were broken in small pieces and dropped in. The tools were run often to be sure that the hole was not bridged



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Ohio Oil Company
Address Box 710, McPherson, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bruce Aug (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bruce Aug

Box 710 McPherson Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4 day of Nov. 19 38.

My commission expires Feb. 11, 1941.

A. J. McClintick
Notary Public.