

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

SW NW
Well Location ~~330-N~~ ~~100-3-W~~ of Cor. Sec. 15 Twp. 26 Rge. 9 (E) (W) West

Field Name (if any) Lerado County Reno

Lease (Farm Name) Mauck Well No. 2

Was well log filed with application? Yes If not, explain circumstances and give available date (Use an additional sheet if necessary)

Log attached.

Date and hour plugging is desired to begin As soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired (Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner

J. A. Deffeyes Address Box 751, Great Bend, Kansas

Name of well owner or Acting Agent Cities Service Oil Company

Address Bartlesville, Oklahoma

Invoice covering assessment for plugging this well should be sent to:


Cities Service Oil Co. Address Box 751, Great Bend, Kansas

and payment will be guaranteed by applicant.

[Signature]
Operator or Acting Agent

Date February 22, 1943

FILE 15-269-W
BOOK PAGE 64 LINE 43



2-23-43



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS
February 25, 1943

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 2
Farm Mauck
Description SE NW 15-26-9W
County Reno
File 64-43

Cities Service Oil Co.
Box 751
Great Bend, Kansas

Dear Sirs:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: Ruel Durkee
Box 597
McPherson, Kansas

WELL RECORD

Company Cities Service Oil Co.
 (Formerly Empire O. & R. Co.) Well No. 2 Farm Mauck
 Location 330' North and 1004.3' West of Center Sec. 15 T. 26 R. 9W
 Elevation _____ County Reno State Kansas
 Drig. Comm. October 28, 1936 Contractor Corbett-Barbour Drilling Co.
 Drig. Comp. December 7, 1936 Acid _____
 T. D. 4163' Initial Prod. 5819 oil, 24 hrs.

CASING RECORD:

12 1/2" 306' cem. with 300 sx Lehigh
 7" OD 4154 1/2' cem. with 325 sx.

FORMATION RECORD:

surface sand	18
water sand	155
shale	182
red rock	260
sand & shells	280
water sand & gravel	290
shells	306
red rock & shells	373
shale & shells	540
lime	571
shale & shells	900
salt	966
salt & shale	1287
shale	1298
lime	1654
broken lime	1668
shale & shells	1700
lime	1794
lime & shale	1811
shale & shells	1821
lime	1857
shale	1870
sandy lime	1882
lime	1980
broken lime & shale	2040
lime	2058
lime & shale breaks	2142
shale & shells	2279
lime & shale	2340
sandy lime	2435
lime broken	2450
shale & shells	2541
shale	2550
lime broken	2594
lime & shale	2688
shale & shells	2830
lime & shale	2873
lime	2909
shale & shells	2953

shale	3049
lime	3088
lime & shale	3114
shale	3121
lime	3200
lime broken	3281
S. L. M. correction	3281= 3292
shale & lime	3355
lime broken	3393
lime	3432
lime hard	3474
lime sandy	3485
lime	3489
dolomite	3514
lime	3528
lime & hard sand	3565
lime	3690
shale	3700
lime	3778
lime broken	3813
lime & shale	3849
lime & bentonite	3882
lime	3890
chert	3903
chat	3954
lime	3972
shale	3990
mud and shale	4010
shale & shells	4048
shale	4095
lime	4100
shale	4110
S. L. M. correction	4110=4111
shale	4132
Cored 4132-4156 1/2' corrected.	
shale	4146 1/2
brown lime	4151 1/2
shale	4154 1/2
dolomitic limestone	4156 1/2
dolomite lime	4163 T. D.
Top Viola	4154 1/2'
T. D.	4163'
Above taken at an elev. of 1690' Orig.	
D. F. Meas.	