

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

NE SE NW

WELL PLUGGING APPLICATION FORM

Well Location NE NW (1010'-N) 330'-W of Cent Sec. 15 Twp. 26 Rge. 9 (E) (W) West

Field Name (if any) Lerado County Reno

Lease (Farm Name) Mauck Well No. 1

Was well log filed with application? Yes If not, explain circumstances and give available date (Use an additional sheet if necessary)

Log attached.

Date and hour plugging is desired to begin As soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired (Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner

J. A. Deffeyes Address Box 751, Great Bend, Kansas

Name of well owner or Acting Agent Cities Service Oil Company

Address Bartlesville, Oklahoma

Invoice covering assessment for plugging this well should be sent to:

Cities Service Oil Co. Address Box 751, Great Bend, Kansas

and payment will be guaranteed by applicant.

R. Hauber

Operator or Acting Agent

Date February 22, 1943.

PLUGGING  
FILED  
BOOK PAGE 64 15-26-9-43

STATE CORPORATION COMMISSION  
FEB 23 1943  
CONSERVATION DIVISION  
WICHITA, KANSAS

2-23-43



STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS  
February 23, 1943

IN REPLY PLEASE  
REFER TO THIS  
SUBJECT

Well No. 1  
Farm Mauck  
Description SE NW 15-26-9W  
County Reno  
File 64-42

Cities Service Oil Co.  
Box 751  
Great Bend, Kansas

Dear Sirs:

This letter is your permit to plug  
the above subject well, in accordance  
with the Rules and Regulations of the  
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR  
CONSERVATION DIVISION

HA

BY: J. P. Roberts  
J. P. ROBERTS

NOTICE:

Ruel Durkee  
Box 597  
McPherson, Kansas


Cities Service Oil Co.

# WELL RECORD

(formerly  
Empire Oil & Refining)

Company

No. 1 Farm Mauck



Location 1010'N - 330'W of Cen.

Sec. 15 T. 26 R. 9.

Elevation \_\_\_\_\_ County \_\_\_\_\_

Reno

State Kansas

Date Commenced: 8-15-36

Date Completed 9-24-36

Initial Production 6708 after 6000 gals. aci

Drld. by Corbett & Barbour

T.D. 4151 1/2'

**Casing Record:**

10" 250' Cem. 150 sacks Ash Grove  
7" OD 4142' (4140 1/2' Pres. D.F. Meas.)  
Cem. w/ 310 sacks

**Formation:**

**Depth:**

Sand	130
Red rock	250
Red beds	310
Red rock	470
Shale	528
Red rock & shale	550
Shale & shells	835
Shale & red rock	900
Salt and shells	973
Salt	1175
Salt & shale	1190
Salt	1215
Shale & lime	1256
Shale & shells	1368
Broken lime	1420
Shale & shells	1440
Lime	1465
Shale	1510
Lime	1535
Broken lime	1580
Broken lime & shale	1657
Shale	1760
Shale & lime	1780
Lime	1843
Shale & shells	1904
Shale	2005
Shale & shells	2067
Shale & red rock	2170
Shale	2294
Shale & red rock	2358
Shale	2424
Lime	2450
Shale & shells	2575
Shale & red rock	2643
Shale & shells	2923
Shale & lime broken	3043
Lime	3103
Shale	3199
Shale and broken lime S.S.O.	3287

**Formation:**

**Depth:**

Broken line	3345
Line	3382
S.L.M. Correction	3382=3385
(Good sat. 3401-3407')	
Lime	3785
Lime and shale	3808
Shale	3850
V.C. shale	3883
S.L.M. correction	3883=3885
Chert	3922
Lime	3929
Hard lime	3952
Lime	3963
Broken lime	3970
Shale	4023
Shale & shells	4054
Shale	4087
Shale and shells	4120
S.L.M. (Measured drill pipe)	4120=4111
Shale	4120
Shale, gray, green (cored)	4136
Lime, dense, brown	4139
Shale, grey, green (cored)	4142
S.L.M. Corr. (Rotary Table)	4142=4142
Corr. Rotary Table to	
Derrick Floor	4143=4142
Viola lime	4151'

**Note:**

Derrick floor lowered 1 1/2' giving the following measurement:

Rotary D.F. Meas.		Present	
Elev.	1685'	Elev.	1685'
T.V.L.	4142	T.V.L.	4142
Pen.	9 1/2'	Pen.	9 1/2'
T.D.	4151 1/2'	T.D.	4151 1/2'

Acidized 2000 gals. Dowell xx 10-14-

Depth	Slope	Depth	
400'	1 1/2°	3000'	
800'	1 1/2°	3810'	
1500'	1°		
2000'	1°		

DRILLING  
 FILE 15 269 9/11  
 EQU. PAGE 64 LINE 42

