

RECEIVED
KANSAS CORPORATION COMMISSION

FORM CP-1
Rev. 03/92

JAN 25 1995

1-25-95

CONSERVATION DIVISION
WICHITA, KS

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-047-20,254.000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR F. G. Holl Company I.L.C. KCC LICENSE # 5056 *6.95*
(owner/company name) (operator's)

ADDRESS 6427 E Kellogg P.O. Box 780167 CITY Wichita

STATE Kansas ZIP CODE 67278-0167 CONTACT PHONE # (316) 684-8481

LEASE MAYHEW A WELL# 1-4 SEC. 4 T. 26 R. 16W (East/West)

NW S/2 LOT 4 SPOT LOCATION/QQQQ COUNTY Edwards

1880' FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

330' FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE None SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8" SET AT 331' CEMENTED WITH 250 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 4516' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4458 to 4462 Kinderhook Sand

ELEVATION 2091KB T.D. 4537' PSTD 4480' ANHYDRITE DEPTH NA
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Heavy Mud, Hulls, Cement and Halliburton Plug.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Art Merrick PHONE# (316) 995-3171

ADDRESS P.O. Box 158 City/State Belpre, Ks. 67519

PLUGGING CONTRACTOR Pratt Well Service KCC LICENSE # 5893 *6.95*

(company name) (contractor's)
ADDRESS P.O. Box 847 Pratt, Ks. 67124 PHONE # () (316) 672-2531

PROPOSED DATE AND HOUR OF PLUGGING (if known?) Not Known

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/24/95 AUTHORIZED OPERATOR/AGENT: *Steven H. Vogel*
(signature)



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 26, 1995

F G Holl Company L L C
6427 E Kellogg P O Box 780167
Wichita KS 67278-0167

Mayhew A #1-4
API 15-047-20,254
1880 FNL 330 FWL
Sec. 04-26S-16W
Edwards County

Dear Art Merrick,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Handwritten signature of David P. Williams in cursive.

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - MAYHEW #1
Located: C 57 NE, Section 4-26E-16W, Edwards County, Kansas

OWNER: F. C. Koll, Barton A. Koll and Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 21, 1977
COMPLETED: April 30, 1977

TOTAL DEPTH: 4517'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 150 Sand and Clay	Ran 8 joints used 28#, 8 5/8" casing, 319.57' set at 331' K.B. with 250 sacks 60/40 Pozmix with 3% cc. Plug down at 6:40 AM, 4-21-77, by Howco.
150 - 333 Sand, Clay and Shale	
333 - 960 Shale, Sand and Red Bed	
960 - 1090 Shale and Sand	
1090 - 1101 Anhydrite	
1101 - 2045 Shale and Shells	
2045 - 2100 Shale and Lime Stgs.	
2100 - 3935 Lime and Shale	
3935 - 4160 Lime	
4160 - 4390 Lime and Shale	
4390 - 4446 Lime, Shale and Chert	
4446 - 4472 Shale, Lime and Sand	
4472 - 4492 Sand and Shale	
4492 - 4517 Shale, Lime and Chert	Ran 139 joints used 10.5#, 4 1/2" casing, 4517.93' set at 4516' K.B. with 125 sacks Pozmix with 2% gel and 18% salt and 3/4# CPR-2 and 5# Gilsomite and 1/8# Flocele and 1/8# Tuffiter per sack. 500 gal. mud flush ahead of cement. Plug down at 10:30 AM, 4-30-77, by Howco.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 25 1995
CONSERVATION DIVISION
WICHITA, KS